

KANSAS

Form CP-3  
Rev. 6-26-62

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

AUG 14 1967

08-14-1967

CONSERVATION DIVISION  
WICHITA, KANSAS

15-163-20044-00-00

Operator's Full Name National Associated Petroleum Company

Complete Address: 502 Ritz Building Tulsa, Oklahoma

Lease Name Alva E. Beck Well No. 1

Location NE NE SE Sec. 11 Twp. 7 Rge. 17 (E) (W)X

County Rooks Total Depth 3388

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated:     

Plugging Contractor: Thoroughbred Drilling Co.

Address: Tulsa, Okla. License No.     

Operation Completed: Hour 12 M Day 12 Month 8 Year 1967

The Above well was plugged as follows:

RTD 3388' 8 5/8 csg set at 1242' cwc.

Gunned pits, circulated heavy mud, set cementing plug at 720' and displaced 80 sc cem.  
thru drill pipe. Heavy mud to 200' set cementing plug and displaced 20 sc cement thru  
drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 10 sc cement to base  
of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Ron J. Massey  
Well Plugging Supervisor

DATE 8/14/67

INV. NO. 6124-W