

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-163-21, 791-00-00

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name LIBERTY ENTERPRISES INC.

Complete Address 308 WEST MILL, PLAINVILLE, MO. 67663

Lease Name TRILEY Well No. #6

Location SE-SE-SE Sec. 20 Twp. 7^S Rge. 17^W (East)(West)

County ROOS. Total Depth 3400 FT

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor PIONEER DRUG. (JOHN WALKER)

Address 308 WEST MILL, PLAINVILLE, MO. 67663 License No. _____

Operation Completed: Hour: 2:30 AM Day: 19th Month: SEPT. Year: 1982

Plugging Operations attended by Agent?: All Part None

(By Allied)

The above well was plugged as follows:

8 5/8" - 261 FT SP. CASING w/ 165ST 60/40 PERMIX - 2% GEL. - 3% CA-CL.
ORDERED 160ST 50/50 PERMIX 6% GEL. 3% CA-CL. AND 8 5/8" PLUG.
SPOT WITH DRILL STEM - WITH HEAVY MUD BETWEEN ALL PLUGS.
1ST PLUG @ 840 FT w/ 100ST CNT.
2ND PLUG @ 270 FT w/ 40ST CNT.
3RD PLUG - ^{SOLID BRIDGE} FULL'S - PLUG. @ 40 FT TO 10ST CNT.
10ST IN RAT HOLE (CIRCULATE)

CEMENTED BY ALLIED CNT.

Amount of Surface Casing: 261 FT

I hereby certify that the above plugging instructions were given as herein stated.

Signed: [Signature]
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

RECEIVED
STATE CORPORATION COMMISSION

SEP 27 1982

CONSERVATION DIVISION
Wichita, Kansas

Signed: _____
Conservation Division Agent

INVOICED

DATE 10-20-82

INVOICE 1415-W

[Handwritten mark]