

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT REPORT

API Number 15-163-91,619-00-00

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Lucky Lady Oil Co.

Complete Address R.J. Taylor - Box 465 Cimarron, KS 67835

Lease Name Fenton Well No. #1

Location E2 SE4 Sec. 15 Twp. 7 Rge. 17 (East) (West)

County Rooks Total Depth 3477

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Circle M Drilling Co. (Sam Williams)

Address Chertin, Kansas License No. _____

Operation Completed: Hour: 1:30 Day: 5 Month: 4 Year: 19 82

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows:

8 1/2" @ 1105' w/500 ^{250 sx lite} sx - circ - 27 gal 32 cc (Halliburton)
(total 750 sx)

Lost Circ @ 3477' (mud wt. 11.2#) mix mud
circ back.

Ordered 130 sx 50/50 poz mix 40 gal - 32 cc & 8 1/2" plug

Spotted 70 sx @ 1200'; 40 sx @ 300'

10 sx @ 40'-0 on solid bidge - 10 sx in Rat Hole
(Halliburton)

Amount of Surface Casing: 1105

I hereby certify that the above plugging instructions were given as herein stated.

Signed: Dennis L. Hamel
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

Went to Banner Drilling! Not ready to plug - Drove to Circle M
rig to check - 10-15 sx dry cnt. on ground - rat hole not plugged -
Called Circle M Office had them recall Halliburton back
to location - pumped cnt in Rat hole! - Plugged @

Signed: Dennis L. Hamel
Conservation Division Agent

10:30 AM - 4-5-82

INVOICED

DATE 4-16-82

INV. NO. 9943-10

RECEIVED
STATE CORPORATION COMMISSION

APR 13 1982
04-13-1982
CONSERVATION DIVISION
Wichita, Kansas