

B

DISTRICT CONSERVATION AGENT'S REPORT

15-163-02667-00-00

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 117-30

LOCATION CSW-SW

SEC. 26 TWP. 7 RGE. 19-W

Dry Hole X Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Clayton

Operator Cooperative Refinery Assoc Address 402-Schwartz Bldg - Wichita

Field _____ County Roos

Total Depth 3096 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 8 1/2 - 106 ft - Cemented all around.

This well was never completed - Tools lost at 2740 ft

& could not recover - 5 1/2 in casing was set at 3058 ft

& cemented - Put in Plug & bridge at 2725 x 10 Sacks

of cement with Munch Boiler - Shot off 5 1/2 casing at 2400 ft

& pulled same - Filled hole with Heavy Mud to 106 ft

Plug set at 106 ft & 10 sacks of cement - Hole then

filled with Mud to 20 ft of

Surface - 10 Sacks of cement

used in Surface Plug

Betts & Linnemiller - Pipe Pullers.

C. R. Stough
District Conservation Agent

Date 7-17-47

7-19-47