



ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg.

212 N. Market

WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

15-179-20149-00-00

RECEIVED
 STATE CORPORATION COMMISSION
 OCT 24 1968
 CONSERVATION DIVISION
 Wichita, Kansas
 10-24-1968

J. P. Roberts
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Bob Delaney of Leben Drilling, Incorporated has this date requested permission to plug the following described well:

Mr. Delaney guarantees payment of the plugging fee.

Operator's full Name: Three "G" Oil, Incorporated,

Complete Address: 1101 Wichita Plaza Building, Wichita, Kansas.

Lease Name: Sidesinger Well No. 1

Location: SE-SE-NE Sec. 35 Twp. 6 Rge. (E)(W) 27

County: Sheridan Total Depth 4150 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Delaney was instructed to plug the well as follows:

317'--8 5/8" Surface casing, cement circulated.
Top of Dakota section @ 1250'.

Circulate hole with heavy mud. Pull DP to 1470' and displace 100 Sx. cement thru DP. Pull DP to 335' and displace 20 Sx. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of cellar.

Very truly yours,

Conservation Division Agent