



ROBERT B. DOCKING Governor  
 DALE E. SAFFELS Chairman  
 JULES V. DOTY Commissioner  
 JAMES O. GREENLEAF Commissioner  
 RAYMOND B. HARVEY Secretary  
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

RECEIVED  
 STATE CORPORATION COMMISSION  
 OCT 21 1968  
 CONSERVATION DIVISION  
 Wichita, Kansas  
 10-21-1968

J. P. Roberts  
 Administrator  
 500 Insurance Building  
 Wichita, Kansas 67202

Dear Sir:

Mr. Ray Blandin of Cities Service Oil Company, has this date requested permission to plug the following described well:

Mr. Blandin guarantees payment of the plugging fee.

Operator's full Name: Cities Service Oil Company

Complete Address: Box #553, Russell, Kansas

Lease Name: Adell Unit Well No. 404-W

Location: CN/2-NW-NE Sec. 13 Twp. 6 Rge. (E)(W) 27

County: Sheridan Total Depth 3775' Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Blandin was instructed to plug the well as follows:

217'--8 5/8" Surface casing, cement circulated with 150 Sx.  
3775'--5 1/2" Production casing cemented on bottom with 125 Sx. DV tool set in anhydrite with cement to surface. Well plugged back to 3722'  
Top perforations @ 3633'.

Run tubing to bottom and displace 20 Sx. cement on bottom Pull tubing above cement and circulate heavy gel mud. Pull tubing to 1280' and displace 40 Sx. cement. Pull tubing to 240' and displace 20 Sx. cement. Pull tubing to 30' and displace 5 Sx. cement

Very truly yours,

W. S. Nichols  
 Conservation Division Agent