



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

12-23-1971  
RECEIVED  
STATE CORPORATION COMMISSION  
DEC 23 1971  
CONSERVATION DIVISION  
Wichita, Kansas

15-179-05516-00-00

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. John Glenn of Pipe Pullers, Incorporated has this date requested permission to plug the following described well:

Mr. Glenn guarantees payment of the plugging fee.

Operator's full Name: Continental Oil Company,

Complete Address: 3535 NW 58th Street, Oklahoma City, Oklahoma.

Lease Name: Adell LKC Unit Well No. 209

Location: SW-SE-NW Sec. 12 Twp. 6 Rge. (E)(W) 27

County: Sheridan Total Depth 3930' Oil Well

Gas Well  Input Well X SWD Well  D & A  Lost Hole

Mr. Glenn was instructed to plug the well as follows:

203'--8 5/8" Surface casing, cement circulated with 200 Sx.  
3950'--5 1/2" Production casing cemented on bottom with 225 Sx. Well plugged back to 3903'. Top of perforations @ 3668'. (Continental requested bottom be plugged off to their specifications). Run tubing to 3880' and displace 1 sack hulls and 50 sx cement thru tubing from 3880' to 3480'. Pull 5 1/2" casing and squeeze well with 5 sack hulls, 30 sacks gel and 150 Cu. Ft. cement, staged.

Very truly yours,

M. L. Finkel  
Conservation Division Agent