

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

15-179-20382-00-00

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202RECEIVED
STATE CORPORATION COMMISSION
JUN 4 1974
06-04-1974
CONSERVATION DIVISION
Wichita, Kansas

Dear Sir:

Mr. Joe Weber of Abercrombie Drilling, Inc., has this
date requested permission to plug the following described well:Mr. Weber guarantees payment of the plugging fee.Operator's full Name: F & M Oil Company, Incorporated,Complete Address: 603 Union Center, Wichita, Kansas.Lease Name: Schruben Well No. 1Location: SE-NW-NW Sec. 34 Twp. 6 Rge. (E)(W) 27County: Sheridan Total Depth 4110' Oil Well Gas Well Input Well SWD Well D & A X Lost Hole Mr. Weber was instructed to plug the well as follows:345'--8 5/8" Surface casing, cement circulated with 225 Sx.
Top of Dakota section @ 1250'.Circulate hole with heavy mud. Pull DP to 1450' and displace 110 Cu. Ft.
cement thru DP. Pull DP to 345' and displace 30 Cu. Ft. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to
bottom of cellar.

Very truly yours,

Conservation Division Agent