



ROBERT B. DOCKING Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
DALE E. SAFFELS Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

RECEIVED
MAY 6 1968
CONSERVATION DIVISION
Wichita, Kansas
05-06-1968

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir: 15-179-20095-00-00

Mr. Jack Flake of Woodman & Iannitti Drilling Coas this date requested permission to plug the following described well:

Mr. Flake guarantees payment of the plugging fee.

Operator's full Name: Woodman & Iannitti Oil Company,

Complete Address: 706 Union National Building, Wichita, Kansas.

Lease Name: Coulter Well No. 1

Location: SW-SW-NW Sec. 28 Twp. 6 Rge. (E)(W) 27

County: Sheridan Total Depth 4150 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Flake was instructed to plug the well as follows:

327'--8 5/8" Surface pipe, cement circulated with 200 Sx.
Dakota Section top @ 1300'.

Circulate hole with heavy mud. Pull DP to 1530' and displace 100 Sx.
cement thru DP. Pull DP to 360' and displace 20 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

Very truly yours,

W. L. Nichols
Conservation Division Agent