

State of Kansas



15-193-20052-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian  
WICHITA, KANSAS 67217

RECEIVED  
STATE CORPORATION COMMISSION

OCT 21 1974

CONSERVATION DIVISION  
Wichita, Kansas

10-21-74

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. R. L. Sixbury of Murfin Drilling Company has this

date requested permission to plug the following described well:

Mr. Sixbury guarantees payment of the plugging fee.

Operator's full Name: Murfin Drilling Company,

Complete Address: 617 Union Center, Wichita, Kansas.

Lease Name: Shughart Well No. 1

Location: CNW-NW Sec. 11 Twp. 6 Rge. (E)(W) 33

County: Thomas Total Depth 2795' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Sixbury was instructed to plug the well as follows:

262'--8 5/8" Surface casing, cement circulated with 225 Sx.  
Top of Dakota section @ 1550'.

Circulate hole with heavy mud. Pull DP to 1775' and displace 110 Cu. Ft.  
cement thru DP. Pull DP to 275' and displace 30 Cu. Ft. cement thru DP.  
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to  
bottom of cellar.

Very truly yours,

*R. L. Dickola*  
Conservation Division Agent