



15-193-20072-00-00

ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION
 MAR 17 1969
 CONSERVATION DIVISION
 Wichita, Kansas
 3-17-69

J. Lewis Brock
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Norman Rodie of Rains & Williamson Oil Co. Inc has this date requested permission to plug the following described well:

Mr. Rodie guarantees payment of the plugging fee.

Operator's full Name: Gary Sandlin, E. Doyle Huckaby, Trustee and South Texas Development Company,
 Complete Address: 818 Midland Savings Building, Denver, Colorado.

Lease Name: Franklin Well No. 1

Location: CNW-NE Sec. 11 Twp. 6 Rge. (E)(W) 33

County: Thomas Total Depth 4609' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Rodie was instructed to plug the well as follows:

253'--8 5/8" Surface casing, cement circulated with 175 Sx.

Circulate hole with heavy mud. Pull DP to 1850 And displace 100 Sx. cement thru DP. Pull DP to 285' and displace 25 Sx. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of cellar.

Very truly yours,

A. S. Nichols

Conservation Division Agent