



15-193-20029-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JUN 2 1970
CONSERVATION DIVISION
Wichita, Kansas
62-70

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Art Hunt of Rains & Williamson Oil Co. Inc. has this date requested permission to plug the following described well:

Mr. Hunt guarantees payment of the plugging fee.

Operator's full Name: Mull Drilling Company, Incorporated,

Complete Address: 1425 Wichita Plaza Building, Wichita, Kansas.

Lease Name: Turner Well No. 1

Location: NW-SE Sec. 2 Twp. 6 Rge. (E)(W) 33

County: Thomas Total Depth 2915' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Hunt was instructed to plug the well as follows:

289'--8 5/8" Surface casing, cement circulated with 200 Sx.
Top of Dakota section @ 1450'.

Circulate hole with heavy mud. Pull DP to 1650' and displace 100 Sx.
cement thru DP. Pull DP to 335' and displace 30 Sx. cement thru DP.
Landowner has requested top hole be left open for development as a fresh
water well. Pull DP to 260' and circulate clear water to clean upper
hole of cement and mud.

Very truly yours,

M. S. Nichols
Conservation Division Agent