

*24*

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COM. Div.  
MAY 6 1968  
CONSERVATION DIVISION  
Wichita, Kansas  
05-06-1968

*15-179-20095-00-00*

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Woodman & Iannitti Oil Company,

Complete Address: 706 Union National Bank Building, Wichita, Kansas.

Lease Name Coulter Well No. 1

Location SW-SW-NW Sec. 28 Twp. 6 Rge. (E) (W) 27

County Sheridan Total Depth 4150

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated:     

Plugging Contractor: Woodman & Iannitti Drilling Company,

Address: 706 Union National Bldg., Wichita, Kans. License No.     

Operation Completed: Hour 2:00 PM Day 29 Month 4 Year 1968

The Above well was plugged as follows:

327'--8 5/8" Surface pipe, cement circulated with 200 Sx.  
Top of Dakota Section @ 1300'.

Circulated hole with heavy mud. Pulled DP to 1530' and displaced 100 Sx. cement  
thru DP from 1530' to 1200'. Pulled DP to 360' and displaced 20 Sx. cement thru DP.  
from 360' to 300'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement  
to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *A. L. Diebel*  
Well Plugging Supervisor

INVOICED

DATE 5/9/68  
INV. NO. 947115W