

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-179 20149-00-00

RECEIVED
STATE CORPORATION COMMISSION
OCT 24 1968
CONSERVATION DIVISION
Wichita, Kansas
10-24-1968

Operator's Full Name Three "G" Oil, Incorporated,

Complete Address: 1101 Wichita Plaza Building, Wichita, Kansas.

Lease Name Sidesinger Well No. 1

Location SE-SE-NE Sec. 35 Twp. 6 Rge. (E) (W) 27

County Sheridan Total Depth 1150'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Leben Drilling, Incorporated,

Address: Box #486, Great Bend, Kansas. License No.

Operation Completed: Hour 12:00 M Day 22 Month 10 Year 1968

The Above well was plugged as follows:

317'--8 5/8" Surface casing, cement circulated.
Top of Dakota section @ 1250'.

Circulated hole with heavy mud Pulled DP to 1170' and displaced 100 Sx. cement from

1170' to 1145'. Pulled DP to 335' and displaced 20 Sx. cement from 335' to 275'.

Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement from 40' to bottom
of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: W. L. Nichols
Well Plugging Supervisor

INVOICED

DATE 10/24/68

INV. NO. 8691-42