



Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUN 4 1974
06-04-1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

15-179-20382-00-00

Operator's Full Name F & M Oil Company, Incorporated,
Complete Address 603 Union Center, Wichita, Kansas.
Lease Name Schruben Well No. 1
Location SE-NW-NW Sec. 34 Twp. 6 Rge. (E) (W) 27
County Sheridan Total Depth 4110'
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated
Plugging Contractor Abercrombie Drilling, Incorporated,
Address 801 Union Center, Wichita, Kansas. License No.
Operation Completed: Hour 9:45 PM Day 30 Month 5 Year 1974

The above well was plugged as follows:

345'---8 5/8" Surface casing, cement circulated with 225 Sx.
Top of Dakota section @ 1250'.

Circulated hole with heavy mud. Pulled DP to 1450' and displaced 110 Cu. Ft. cement
thru DP from 1450' to 1125'. Pulled DP to 345' and displaced 30 Cu. Ft. cement thru
DP from 345' to 270'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: W. G. Dickols
Well Plugging Supervisor

DATE 6/5/74
INV. NO. 9244-W