

15-179-05153-00-00

Form CP-3  
Rev. 6-26-62

KANSAS

*al*

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 21 1968  
CONSERVATION DIVISION  
Wichita, Kansas  
10-21-1968

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Cities Service Oil Company,

Complete Address: Box #553, Russell, Kansas.

Lease Name Adell Unit Well No. 404-W

Location CN/2-NW-NE Sec. 13 Twp. 6 Rge. (E) (W) 27

County Sheridan Total Depth 3775'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Halliburton Services,

Address: Box #339, Hays, Kansas. License No. \_\_\_\_\_

Operation Completed: Hour 1:00PM Day 14 Month 10 Year 1968

The Above well was plugged as follows:

217'--8 5/8" Surface casing, cement circulated with 150 Sx.  
3775'--5 1/2" Production casing cemented on bottom with 125 Sx. DV tool set in anhydrite  
with cement to surface. Well plugged back to 3722', top perforations @ 3633'.  
Ran tubing to bottom and displaced 20 Sx. cement from 3722' to 3562. Pulled tubing to  
3510' and circulated heavy gel mud using 25 sacks gel. Pulled tubing to 1280' and dis-  
placed 40 Sx. cement from 1280' to 960'. Pulled tubing to 240' and displaced 10 Sx.  
cement thru tubing from 240' to 160'. Pulled tubing to 30' and displaced 5 Sx. cement  
to surface.

I hereby certify that the above well was plugged as herein stated.

Signed: *M. L. Nichols*  
Well Plugging Supervisor

INVOICED

DATE 10/21/68  
INV. NO. 8667-4