

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

15-179-05156-00-01
API Number 15-~~none~~

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Conoco Inc.

Complete Address Box 2197 Houston TX.

Lease Name Adell Well No. 206

Location SE NW NW Sec. 12 Twp. 6 Rge. 27 (East) (West)

County Sheridan Total Depth 3850

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Plainville oil well service & Halliburton

Address _____ License No. _____

Operation Completed: Hour: 2 PM Day: 17 Month: 3 Year: 19 82

Plugging Operations attended by Agent?: All Part _____ None _____

The above well was plugged as follows:

Hole cleaned out to 210 ft. - new 10 3/4" pipe set to 200'
tried to run out old 6" casing and couldn't so loaded
top 200 ft of hole and casing with 90 sp common cement
with 2 7/8" tubing left in hole and cemented in to squeeze
through as there was no old surface pipe left. 2nd job we
squeezed down hole with 500 sp common cement thru
2 7/8 tubing and old 6" casing. old 6" casing was set with 300 sp
common cement at 3849 4 1/2" casing liner was set at 4023 with 600 sp

Amount of Surface Casing: 210' ~~404 sp~~

I hereby certify that the above plugging instructions were given as herein stated.

Signed: Carl Goodnow
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

Signed: _____
Conservation Division Agent

INVOICED
DATE 3-26-82
9780-W

RECEIVED
STATE CORPORATION COMMISSION
MAR 22 1982
CONSERVATION DIVISION
Wichita Kansas