

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

REC'D  
11-~~18~~ 21-74

Operator's Full Name Murfin Drilling Company, 15-193-20052-00-00  
 Complete Address 617 Union Center, Wichita, Kansas.  
 Lease Name Shughart Well No. 1  
 Location CNW-NW Sec. 11 Twp. 6 Rge. (E) (W)33  
 County Thomas Total Depth 2795'  
 Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X  
 Other well as hereafter indicated         
 Plugging Contractor Above  
 Address        License No.         
 Operation Completed: Hour 8:15 AM Day 15 Month 10 Year 1974

The above well was plugged as follows:

262'--8 5/8" Surface casing, cement circulated with 225 Sx.  
Top of Dakota section @ 1550'.

Circulated hole with heavy mud. Pulled DP to 1775' and displaced 110 Cu. Ft. cement  
thru DP from 1775' to 1450'. Pulled DP to 275' and displaced 30 Cu. Ft. cement thru  
DP from 275' to 200'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.  
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: H. L. Dehals  
Well Plugging Supervisor

INVOICED

DATE 10/23/74  
INV. NO. 167-W