

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-179-05516-00-00

12-23-1971
RECEIVED
STATE CORPORATION COMMISSION
DEC 23 1971
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Continental Oil Company,

Complete Address 3535 NW 58th Street, Oklahoma City, Oklahoma.

Lease Name Adell LKC Unit Well No. 209

Location SW-SE-NW Sec. 12 Twp. 6 Rge. (E) (W) 27

County Sheridan Total Depth 3930'

Abandoned Oil Well Gas Well Input Well X SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Pipe Pullers, Incorporated,

Address Box #486, Ellinwood, Kansas. License No. 462

Operation Completed: Hour 3:30 PM Day 23 Month 12 Year 1971

The above well was plugged as follows:

203'--8 5/8" Surface casing, cement circulated with 200 Sx.
3950'--5 1/2" Production casing cemented on bottom with 225 Sx.

Ran tubing to 3880' and displaced 1 sack hulls and 50 sacks cement thru tubing by
request of Continental. Pulled 5 1/2" casing (925') and squeezed well initially with
5 sacks hulls and 4 sacks gel then 110 Cu. Ft. cement from 1475' to 1150' then 22 sacks
gel from 1150' to 250' and followed with 30 Cu. Ft. cement from 250' to 175' then 4
sacks gel from 175' to 30' and finally 10 Cu. Ft. cement from 30' to bottom of cellar.
Maximum pump-in pressure--300#. Final shut-in pressure--50#. (Plugging by Sun Cementing).

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: W. L. Pichler
Well Plugging Supervisor

DATE 1-7-72

INV. NO. 4899-W