

15-179-00118-00-01

Form CP-3  
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 13 1967  
03-13-1967  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Operator's Full Name Cities Service Oil Company,

Complete Address: Box # 553, Russell, Kansas.

Lease Name Adell Unit Well No. 201-W

Location SE-SE-SE Sec. 12 Twp. 6 Rge. (E) (W) 27

County Sheridan Total Depth 3805

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Halliburton Company,

Address: Hill City, Kansas. License No. \_\_\_\_\_

Operation Completed: Hour 4:30PM Day 6 Month 3 Year 1967

The Above well was plugged as follows:

335'--8 5/8" Surface pipe, cement circulated. 3804' 5 1/2" Production casing cemented. Attempted to pull 2" tubing but packers hung up leaving 32 joints of tubing plus Baker Model "G" and Model "B" packers. Tubing open thru packers. Perforations from 3569' to 3571', 3616' to 3620', 3645' to 3649', 3656' to 3660' and 3740' to 3744'.

Squeezed 5 1/2" casing below packers with 30 Sx. gel followed with 10 Sx. cement. Maximun pump-in pressure 500#. Ran 1" tubing, was unable to get below 750' with 1" tubing. Circulated heavy gel mud from 750' to surface using 10 Sx. gel. Pulled 1" tubing to 330' and circulated cement to surface using 40 Sx. cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 3/13/67  
INV. NO. 4899-W

Signed: A. L. Nichols  
Well Plugging Supervisor