

KANSAS

al

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-193-20029-00-00

RECEIVED
STATE CORPORATION COMMISSION
JUN 2 1970
CONSERVATION DIVISION
Wichita, Kansas
62-70

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Mull Drilling Company, Incorporated,

Complete Address 1625 Wichita Plaza Building, Wichita, Kansas.

Lease Name Turner Well No. 1

Location NW-SE Sec. 2 Twp. 6 Rge. (E) (W) 33

County Thomas Total Depth 2915'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Rains & Williamson Oil Company, Incorporated.

Address 1625 Wichita Plaza Building, Wichita, Kans. License No.

Operation Completed: Hour 5:00 PM Day 28 Month 5 Year 1970

The above well was plugged as follows:

289'--8 5/8" Surface casing, cement circulated with 200 Sx.
Top of Dakota section @ 1450'. Landowner, Mr. B. A. Turner requested top hole in 8 5/8"
casing be left open to be developed as a fresh water well.

Circulated hole with heavy mud, pulled DP to 1650' and displaced 100 Sx. cement thru DP
from 1650' to 1325'. Pulled DP to 335' and displaced 30 Sx. cement thru DP. Pulled DP
to 260' and circulated clear water to clear hole from 260' to surface of any cement or
drilling mud. (Signed Water Well Authorization attached).

I hereby certify that the above well was plugged as herein stated.

Signed: *M. L. Nichols*
Well Plugging Supervisor

INVOICED

DATE 6/2/70
INV. NO. 1984-W



15-193-20029-00-00

ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg.

WICHITA, KANSAS 67202

212 N. Market

RECEIVED
STATE CORPORATION COMMISSION

JUN 2 1970
CONSERVATION DIVISION
Wichita, Kansas

62-70

AUTHORIZATION

The undersigned, owner of the following described land, to

wit: NW-SE of Sec. 2 Twp. 6 Rge. 33 ^EW

Thomas County, Kansas; hereby requests

that Well No. 1 located in Sec 2 of Sec. Twp. 6S

^ERge. 33 W be left open above the fresh water protecting
'100 Sx. Cement from 1650' to 1325'. and 25 Sx Cement from 335' to
bridge set at feet, to be used as a fresh water well. Clear Water from
260' to Surface, circulated.

and I hereby authorize Mull Drilling Company, Inc.,

well owner, to so complete the abandonment of said well.

W. L. Nichols *Mr. Turner*

Witnessed by W. L. Nichols

Mr. Turner
(Land Owner)

Dated at Colby, Kansas, this 29 day of May

 , 1970