

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-163-21841-00-0001  
Spot: CSEWNNE Sec/Twnshp/Rge: 30-7S-17W  
4290 feet from S Section Line, 1650 feet from E Section Line  
Lease/Unit Name: GRIFFITH Well Number: 8  
County: ROOKS Total Vertical Depth: 3355 feet

Operator License No.: 7076  
Op Name: BLACK DIAMOND OIL, INC.  
Address: PO BOX 641  
HAYS, KS 67601

Conductor Pipe: Size feet:  
Surface Casing: Size 8.625 feet: 1244 425 SX CMT  
Production: Size 5.5 feet: 3366 140 SX CMT  
Liner: Size feet:

\$109.04

Well Type: OIL UIC Docket No: Date/Time to Plug: 09/05/2001 9:00 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: Ordered out 250 sxs 60/40 pozmix - 10% gel - 400# hulls.  
Perfs 3250' - 3255'.  
Sand back to 3192' with 5 sxs cement on top.

Plugging Proposal Received By: HERB DEINES Witness Type: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 09/05/2001 12:00 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Sanded back to 3192'.  
Shot 5 1/2" casing at 2000' - 1600' - 1200'. No recovery.  
Shot pipe free at 600'.  
Allied pumped 100 sxs with 400# hulls - cement circulated.  
Pulled casing out.  
Allied pressured up 8 5/8".  
Max. P.S.I. 1000#. S.I.P. 1000#.  
Note: Pressures indicate prior cement squeezes.

RECEIVED  
SEP 13 2001  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed Richard Williams  
(TECHNICIAN)

INVOICED

Form CP-2/3

DATE 9-13-01

INV. NO. 2002060459

SEP 12 2001

RIM OIL COMPANY  
512 S WYOMING

#8 GRIFFITH

30-7-17W  
SE NW NE

PLAINVILLE, KS 67663

CONTR PIONEER DRILLING CO INC CTY ROOKS

GEOL \_\_\_\_\_ FIELD RIFFE

|   |   |
|---|---|
| + | + |
| + | + |

ELV 1788 KB SPD 11/12/82 CARD ISSUED 2/10/83 IP P 75 BOPD, NW  
1783 GL ARB 3285-3288

API 15-163-21,841

| SMP | Tops | Depth/Datum |
|-----|------|-------------|
| ARB |      | 3247-1459   |
| RTD |      | 3335-1547   |

8 5/8 " 1244/450SX; 5 1/2 " 3334/140SX  
NO DST'S  
MICT - CO, PF (ARB) 3285-88, TSTD GSO, NAT, POP, P 75  
BOPD, NW (GR 24), 1/2/83

INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS