

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-22484-00-00
Spot: S2SWNWNE Sec/Twnshp/Rge: 20-16S-13W
4240 feet from S Section Line, 2310 feet from E Section Line
Lease Name: PRUSA Well #: 9A
County: BARTON Total Vertical Depth: 3404 feet

Operator License No.: 5259
Op Name: MAI OIL OPERATIONS, INC.
Address: 4514 COLE AVE., STE 740, LB 30
DALLAS, TX 75205

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3403	0	150 SX CMT
SURF	8.625	327	0	185 SX CMT

63
#110

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/30/2005 9:00 AM
Plug Co. License No.: 7049 Plug Co. Name: RAPID WELL SERVICE INC
Proposal Rcvd. from: ALAN BANGERT Company: MAI OIL OPERATIONS, INC. Phone: (785) 483-2169

Proposed Plugging Method: Ordered out 300 sxs 60/40 pozmix - 10% gel - 1/4# flocele per sack - 600# hulls.
Got outside of the pipe at 1000'. Could not get down.

Plugging Proposal Received By: ROGER MOSES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 09/30/2005 11:30 AM KCC Agent: JAY PFEIFER

Actual Plugging Report:

TIH with tubing - hit bridge at 540' - could not get past - decided to P&A.
At 540' - mixed and circulated cement with 75 sxs.
POOH and topped with 155 sxs cement and 500# hulls.
Max. P.S.I. 800#. S.I.P. 600#.
Hooked up to the annulus and pumped 45 sxs cement with 100# hulls.
Max. P.S.I. 400#. S.I.P. 200#.


Perfs:

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed



(TECHNICIAN)

INVOICED

DATE 10-6-05

UV ID 2006010134

RECEIVED

OCT 06 2005

KCC WICHITA

OCT 03 2005

