

3 022848

15-001.02017-0000

To:

STATE CORPORATION COMMISSION

Wichita State Office Bldg. - PLUGGING SECTION

130 S. Market, Room 2078

Wichita, Kansas 67202

API NUMBER CONTROL NO. 20050040-022

SE,SW,SE 1/4 Sec/Twp/Rge S.21-T.25S.-R.18E.

192 feet from south section line

1656 feet from east section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 101Operator: STATE OF KANSAS Fee FundName & FEE FUND PLUGGING

Address _____

AB oil well X Gas Well _____ SWD Well/ Input Well _____

Other well as hereinafter indicated: _____

Plugging Contractor: KEPLEY WELL SERVICE, LLCLic. # 30670Address: 19254 FORD ROAD, CHANUTE, KANSAS 66720Company to plug at: Hour: 1:00P.M. Day: 25 Month: 8 2005Plugging proposal received from: CLAYTON P. TITELCompany Name: KANSAS CORPORATION COMMISSION Phone: 620-432-2300Were: THIS WELL CONSISTED OF 2" CASING TO APPROXIMATELY 845' THATHAD BEEN CEMENTED IN AT T.D. ONLY. THE PLUGGING PROPOSAL WAS TOCIRCULATE AS MUCH OF THE WELL AS POSSIBLE FULL OF CEMENT.

Plugging Proposal Received by:

CLAYTON P. TITEL

Plugging attended by Agent: All _____ Part _____

TECHNICIAN

None XOperations Completed: Hour: 4:00P.M. Day: 25 Month: 8 2005Actual Plugging Report: 1" PIPE WAS RAN INTO THE 2" CASING TO 845'.CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE2" CASING AT SURFACE. THE 1" PIPE WAS REMOVED. 1" PIPE WAS RAN INTO THE2" AND 8" ANNULUS TO 540'. CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENTCIRCULATED FROM THE 8" SURFACE CASING AT SURFACE. THE 1" PIPE WASREMOVED. DISPLACEMENT WAS FILLED FROM SURFACE. 280 SACKS OF CEMENTWERE PUMPED INTO THIS WELL.Remarks: (GPS SESSION PT. NO.22) (THIS WELL WAS NO. 5 ON THE LEASE MAP)

(If additional description is necessary, use BACK of this form.)

I DID NOT observe this plugging.

Signed:

Clayton P. Titel
TECHNICIAN

RECEIVED

SEP 09 2005

KCC WICHITA

Bm