

3 022847

15-001 02016.0000

To:

STATE CORPORATION COMMISSION

Wichita State Office Bldg. - PLUGGING SECTION

130 S. Market, Room 2078

Wichita, Kansas 67202

API NUMBER

CONTROL NO. 20050040-021

SE,SW,SE 1/4

Sec/Twp/Rge

S.21-T.25S.-R.18E.

596 feet from south section line

1670 feet from east section line

TECHNICIAN'S PLUGGING REPORT

Operator License #

101

Lease/Well#

DOTY NO.21

County

ALLEN

Operator: STATE OF KANSAS Fee Fund

Well Total Depth

850'

feet

Name & FEE FUND PLUGGING

Production Pipe:

2

Size Feet 765'

Address

Surface Casing: 8"

Size Feet 20'

AB oil well ☒ Gas Well ☐ SWD Well/ Input Well ☐D & A ☐

Other well as hereinafter indicated:

Plugging Contractor: KEPLEY WELL SERVICE, LLC

Lic. #

30670

Address: 19254 FORD ROAD, CHANUTE, KANSAS 66720

Company to plug at: Hour: 10:A.M. Day: 19 Month: 8 2005

Plugging proposal received from: CLAYTON P. TITEL

Company Name: KANSAS CORPORATION COMMISSION

Phone:

620-432-2300

Were: THIS WELL CONSISTED OF 2" CASING TO APPROXIMATELY 765' THAT

HAD BEEN CEMENTED IN AT T.D. ONLY. THE PLUGGING PROPOSAL WAS TO

CIRCULATE AS MUCH OF THE WELL AS POSSIBLE FULL OF CEMENT.

Plugging Proposal Received by:

CLAYTON P. TITEL

Plugging attended by Agent:

All ☐Part ☐

TECHNICIAN

None ☐X ☒

Operations Completed: Hour:

12:00P.M. Day:

19 Month:

8

2005

Actual Plugging Report:

1" PIPE WAS RAN INTO THE 2" CASING TO 756'.

CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE

2" CASING AT SURFACE. THE 1" PIPE WAS REMOVED. 1" PIPE WAS RAN INTO THE

2" AND 8" ANNULUS TO 450'. CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT

CIRCULATED FROM THE 8" SURFACE CASING AT SURFACE. THE 1" PIPE WAS

REMOVED. DISPLACEMENT WAS FILLED FROM SURFACE. 261 SACKS OF CEMENT

WERE PUMPED INTO THIS WELL.

Remarks: (GPS SESSION PT. NO.21) (THIS WELL WAS NOT ILLUSTRATED ON THE LEASE MAP)

(If additional description is necessary, use BACK of this form.)

I DID NOT observe this plugging.

Signed:

Clayton P. Titel
TECHNICIANRECEIVED
SEP 09 2005
KCC WICHITA