

3 022837

15-001-02015-0000

To:

STATE CORPORATION COMMISSION

Wichita State Office Bldg. - PLUGGING SECTION

130 S. Market, Room 2078
Wichita, Kansas 67202

API NUMBER CONTROL NO. 20050040-019

NE,NW,SE 1/4 Sec/Twp/Rge S.21-T.25S.-R.18E.

2217 feet from south section line

1971 feet from east section line

TECHNICIAN'S PLUGGING REPORT

Operator License #

101

Lease/Well#

DOTY NO.19

County

ALLEN

Operator: STATE OF KANSAS Fee Fund

Well Total Depth 850' feet

Name & FEE FUND PLUGGING

Production Pipe: 4 1/2 Size Feet 750'

Address

Surface Casing: 8" Size Feet 20'

AB oil well ☒ Gas Well ☐ SWD Well/ Input Well ☐ D & A ☐

Other well as hereinafter indicated:

Plugging Contractor: KEPLEY WELL SERVICE, LLC

Lic. # 30670

Address: 19254 FORD ROAD, CHANUTE, KANSAS 66720

Company to plug at: Hour: 3:00P.M. Day: 8 Month: 8 2005

Plugging proposal received from: CLAYTON P. TITEL

Company Name: KANSAS CORPORATION COMMISSION

Phone: 620-432-2300

Were: THIS WELL CONSISTED OF 4 1/2" CASING TO 850' THAT HAD BEEN

CEMENTED IN FROM BOTTOM TO TOP. THE PLUGGING PROPOSAL WAS TO

CIRCULATE THE 4 1/2" CASING FULL OF CEMENT.

Plugging Proposal Received by:

CLAYTON P. TITEL

Plugging attended by Agent: All ☒ Part ☐

TECHNICIAN

None ☐

Operations Completed: Hour: 5:00P.M. Day: 8 Month: 8 2005

Actual Plugging Report: 1" PIPE WAS RAN INTO THE 4 1/2" CASING TO 850'.

CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE

4 1/2" CASING AT SURFACE. THE 1" PIPE WAS REMOVED. DISPLACEMENT WAS

FILLED FROM SURFACE. 168 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

Remarks: (GPS SESSION PT. NO.19) (THIS WELL WAS NOT ILLUSTRATED ON THE LEASE MAP)

(If additional description is necessary, use BACK of this form.)

I DID observe this plugging.

Signed:

Clayton P. Titel
TECHNICIANRECEIVED
SEP 09 2005
KCC WICHITA