

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-189-22487-00-00
Spot: NWNWNW Sec/Twnshp/Rge: 2-31S-38W
324 feet from N Section Line, 269 feet from W Section Line
Lease Name: DUNN Well #: 3-3R
County: STEVENS Total Vertical Depth: 3225 feet

Operator License No.: 4824
Op Name: PIONEER NATURAL RESOURCES USA.
Address: 5205 N. O'CONNOR BLVD.
IRVING, TX 75039

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3221	0	WITH 485 SX CMT
SURF	8.625	640		WITH 375 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 09/19/2005 9:30 AM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGI Phone: (580) 854-6515

Proposed Plugging Method: PUMP 500# HULLS & 25 SX CMT. MUD SPACER TO 1750' & 25 SX CMT. MUD TO 670. CMT FROM 670-0'. CHECK BACKSIDE WITH CMT.

Plugging Proposal Received By: STEVE PFEIFER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/19/2005 11:30 AM KCC Agent: JIM HOLLAND

Actual Plugging Report:

1ST PLUG MIX & PUMP 600# HULLS & 25 SX CMT. TAG TOP OF CMT @ 2080'. 2ND PLUG MUD SPACER TO 1750'. PUMP 25 SX CMT INSIDE 5 1/2". 3RD PLUG MUD SPACER TO 670'. PUMP 95 SX CMT FROM 670' TO 0'. PRESSURED TO 500# & SHUT IN. BACKSIDE FULL.

Perfs:


Top	Bot	Thru	Comments
2494	2795		

RECEIVED
OCT 05 2005
KCC WICHITA

Remarks: USED COMMON CEMENT BY SARGENTS.

Plugged through: CSG

District: 01



Signed

Jim Holland PART II
(TECHNICIAN)

INVOICED
DATE 10-5-05
2006060593

Form CP 2/3