

3 022828

15-001-01930-00-01
~~15-001-0199200-00~~

To:

STATE CORPORATION COMMISSION

Wichita State Office Bldg. - PLUGGING SECTION

130 S. Market, Room 2078

Wichita, Kansas 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 101

Operator: STATE OF KANSAS Fee Fund

Name & FEE FUND PLUGGING

Address _____

AB oil well _____ Gas Well _____ SWD Well/ Input Well _____

Other well as hereinafter indicated: _____

Plugging Contractor: KEPLEY WELL SERVICE, LLC

Lic. # 30670

Address: 19254 FORD ROAD, CHANUTE, KANSAS 66720

Company to plug at: Hour: 10:00AM Day: _____ 12 Month: 8 2005

Plugging proposal received from: CLAYTON P. TITEL

Company Name: KANSAS CORPORATION COMMISSION Phone: 620-432-2300

Were: THIS WELL CONSISTED OF 6 1/4" CASING TO 788' THAT HAD BEEN CEMENTED

IN FROM BOTTOM TO TOP. THE PLUGGING PROPOSAL WAS TO CIRCULATE THE 6 1/4"

CASING FULL OF CEMENT.

Plugging Proposal Received by:

CLAYTON P. TITEL

Plugging attended by Agent: All ☒ Part _____

TECHNICIAN
None _____

Operations Completed: Hour: 12:00P.M. Day: _____ 12 Month: 8 2005

Actual Plugging Report: 1" PIPE WAS RAN INTO THE 6 1/4" CASING TO 850'. CEMENT

WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE 6 1/4" CASING

AT SURFACE. THE 1" PIPE WAS REMOVED. DISPLACEMENT WAS FILLED FROM SURFACE.

105 SACKS OF CEMENT WERE USED TO PLUG THIS WELL.

Remarks: (GPS SESSION PT. NO.1) (THIS WAS NO.1 INJ ON THE INJECTION PERMIT E-24,153)

(If additional description is necessary, use BACK of this form.)

I DID observe this plugging.

Signed:

RECEIVED

AUG 29 2005

KCC WICHITA

Clayton P. Titel
TECHNICIAN

Bum