

3 022798

15.001-02002-000

To:

STATE CORPORATION COMMISSION

Wichita State Office Bldg. - PLUGGING SECTION

130 S. Market, Room 2078

Wichita, Kansas 67202

API NUMBER CONTROL NO. 20050040-013

SE,NW,SE 1/4 Sec/Twp/Rge S.21-T.25S.-R.18E.

1420 feet from south section line

1957 feet from east section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 101Lease/Well# DOTY NO.7 A

County ALLEN

Operator: STATE OF KANSAS Fee Fund

Well Total Depth 875' feet

Name & FEE FUND PLUGGING

Production Pipe: 4 1/2" Size Feet 850

Address

Surface Casing: 8" Size Feet 20'

AB oil well X Gas Well SWD Well/ Input Well D & A Other well as hereinafter indicated:

Plugging Contractor: KEPLEY WELL SERVICE, LLC

Lic. # 30670

Address: 19245 FORD ROAD, CHANUTE, KANSAS 66720

Company to plug at: Hour: 8:00A.M. Day: 29 Month: 7 2005

Plugging proposal received from: CLAYTON P. TITEL

Company Name: KANSAS CORPORATION COMMISSION Phone: 620-431-9212

Were: THIS WELL CONSISTED OF 4 1/2" CASING TO APPROXIMATELY 850' THAT

HAD BEEN CEMENTED IN FROM BOTTOM TO TOP. THE PLUGGING PROPOSAL WAS

TO CIRCULATE THE 4 1/2" CASING FULL OF CEMENT.

Plugging Proposal Received by:

CLAYTON P. TITEL

Plugging attended by Agent: All Part

TECHNICIAN

None X

Operations Completed: Hour: 2:00P.M. Day: 29 Month: 7 2005

Actual Plugging Report: 1" PIPE WAS RAN INTO THE 4 1/2" CASING TO 835'. CEMENT

WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE 4 1/2" CASING AT

SURFACE. THE 1" PIPE WAS REMOVED. DISPLACEMENT WAS FILLED FROM SURFACE.

151 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

Remarks: (GPS SESSION PT. NO.13) (THIS WELL WAS NOT NUMBERED ON THE LEASE MAP)

(If additional description is necessary, use BACK of this form.)

I DID NOT observe this plugging.

Signed:


 TECHNICIAN

RECEIVED

AUG 12 2005

KCC WICHITA

