

3 022814

15-001-02001-0000

To:

STATE CORPORATION COMMISSION

Wichita State Office Bldg. - PLUGGING SECTION

130 S. Market, Room 2078

Wichita, Kansas 67202

API NUMBER CONTROL NO. 20050040-008

NE,NW,SE 1/4 Sec/Twp/Rge S.21-T.25S.-R.18E.

2087 feet from south section line

1409 feet from east section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 101

Operator: STATE OF KANSAS Fee Fund

Name & FEE FUND PLUGGING

Address

AB oil well ☒ Gas Well ☐ SWD Well/ Input Well ☐ D & A ☐

Other well as hereinafter indicated:

Plugging Contractor: KEPLEY WELL SERVICE, LLC

Lic. # 30670

Address: 19245 FORD ROAD, CHANUTE, KANSAS 66720

Company to plug at: Hour: 1:00P.M. Day: 3 Month: 8 2005

Plugging proposal received from: CLAYTON P. TITEL

Company Name: KANSAS CORPORATION COMMISSION Phone: 620-432-2300

Were: THIS WELL CONSISTED OF 4 1/2" CASING TO APPROXIMATELY 850' THAT

HAD BEEN CEMENTED IN FROM T.D. TO 38'. THE PLUGGING PROPOSAL WAS

TO CIRCULATE AS MUCH OF THE WELL AS POSSIBLE FULL OF CEMENT INSIDE

AND OUTSIDE THE 2" CASING.

Plugging Proposal Received by: CLAYTON P. TITEL

Plugging attended by Agent: All ☒ Part ☐

TECHNICIAN
None

Operations Completed: Hour: 4:00P.M. Day: 3 Month: 8 2005

Actual Plugging Report: 1" PIPE WAS RAN INTO THE 4 1/2" CASING TO 850'. CEMENT

WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE 4 1/2" CASING

AT SURFACE. THE 1" PIPE WAS REMOVED. 1" PIPE WAS RAN INTO THE 4 1/2" AND 12"

ANNULUS TO 38'. AT THAT DEPTH A SOLID CEMENT WAS ENCOUNTERED.

CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE 4 1/2"

AND 12" ANNULUS AT SURFACE. THE 1" PIPE WAS REMOVED. DISPLACEMENT WAS

FILLED FROM SURFACE. 224 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

Remarks: (GPS SESSION PT. NO.08) (THIS WELL WAS NOT ISSUSTRATED ON THE LEASE MAP)

(If additional description is necessary, use BACK of this form.)

I DID observe this plugging.

Signed:

Clayton P. Titel
TECHNICIAN

RECEIVED
AUG 17 2005
KCC WICHITA