

3 022799

15-001-02000-0000

To:

STATE CORPORATION COMMISSION

Wichita State Office Bldg. - PLUGGING SECTION

130 S. Market, Room 2078

Wichita, Kansas 67202

API NUMBER CONTROL NO. 20050040-012

SE,NW,SE 1/4 Sec/Twp/Rge S.21-T.25S.-R.18E.

1819 feet from south section line

1664 feet from east section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 101Operator: STATE OF KANSAS Fee FundName & FEE FUND PLUGGING

Address _____

AB oil well X Gas Well _____ SWD Well/ Input Well _____

Other well as hereinafter indicated: _____

Plugging Contractor: KEPLEY WELL SERVICE, LLCLic. # 30670Address: 19245 FORD ROAD, CHANUTE, KANSAS 66720Company to plug at: Hour: 2:30P.M. Day: _____ 29 Month: 7 2005Plugging proposal received from: CLAYTON P. TITELCompany Name: KANSAS CORPORATION COMMISSION Phone: 620-431-9212Were: THIS WELL CONSISTED OF 2" CASING TO APPROXIMATELY 850' THATHAD BEEN CEMENTED IN AT T.D. ONLY. THE PLUGGING PROPOSAL WASTO CIRCULATE AS MUCH OF THE WELL AS POSSIBLE FULL OF CEMENT.

Plugging Proposal Received by:

CLAYTON P. TITEL

Plugging attended by Agent: All _____ Part _____

TECHNICIAN

None XOperations Completed: Hour: 5:30P.M. Day: _____ 29 Month: 7 2005Actual Plugging Report: 1" PIPE WAS RAN INTO THE 2" CASING TO 820'. CEMENTWAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE 2" CASING ATSURFACE. THE 1" PIPE WAS REMOVED. 1" PIPE WAS RAN INTO THE 2" AND 8"ANNULUS TO 285'. CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATEDFROM THE SURFACE CASING AT SURFACE. THE 1" PIPE WAS REMOVED. DISPLACEMENTWAS FILLED FROM SURFCE. 280 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.Remarks: (GPS SESSION PT. NO.12) (THIS WELL WAS NO.7 ON THE LEASE MAP)

(If additional description is necessary, use BACK of this form.)

I DID NOT observe this plugging.

Signed:

Clayton P. Titel
TECHNICIAN

RECEIVED

AUG 12 2005

KCC WICHITA

Bm