

15.001- 62005 0000

3 022830

To:
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, Kansas 67202

API NUMBER CONTROL NO. 20050040-014
SE,NW,SE 1/4 Sec/Twp/Rge S.21-T.25S.-R.18E.
1612 feet from south section line
1870 feet from east section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 101
Operator: STATE OF KANSAS Fee Fund
Name & FEE FUND PLUGGING
Address _____
AB oil well X Gas Well _____ SWD Well/ Input Well _____

Lease/Well# DOTY 10 A
County ALLEN
Well Total Depth 900' feet
Production Pipe: 2" Size Feet 900'
Surface Casing: 10" Size Feet 20'
D & A _____

Other well as hereinafter indicated: _____

Plugging Contractor: KEPLEY WELL SERVICE, LLC Lic. # 30670
Address: 19254 FORD ROAD, CHANUTE, KANSAS 66720

Company to plug at: Hour: 10:00A.M. Day: _____ 9 Month: 8 2005

Plugging proposal received from: CLAYTON P. TITEL

Company Name: KANSAS CORPORATION COMMISSION Phone: 620-432-2300

Were: THIS WELL ORIGINALLY CONSISTED OF 2" CASING TO T.D. THAT HAD ONLY
BEEN PARTIALLY CEMENTED IN. AT SOME TIME IN THE PAST A 3" LINER HAD BEEN
SLEEVED OVER PART OF THE 2" CASING. THE PROPOSAL WAS TO PERFORATE THE
CASING AND TO CIRCULATE AS MUCH OF THE WELL AS POSSIBLE FULL OF CEMENT.

Plugging Proposal Received by: CLAYTON P. TITEL

Plugging attended by Agent: All X Part _____
TECHNICIAN
None _____

Operations Completed: Hour: 12:00P.M. Day: _____ 9 Month: 8 2005

Actual Plugging Report: THE WELLS CASINGS WERE PERFORATED AT 200'
AND AT 500'. 1" PIPE WAS RAN INTO THE 2" CASING TO 850'. CEMENT WAS PUMPED
INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE 2" CASING AT SURFACE. THE
1" PIPE WAS RAMOVED. 1" PIPE WAS RAN INTO THE 3" AND 10" ANNULUS TO 248'. AT
THAT DEPTH A SOLID OBSTRUCTION WAS ENCOUNTERED. CEMENT WAS PUMPED INTO
THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE WELL AT SURFACE. THE 1" PIPE
WAS REMOVED. 182 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

Remarks: (GPS SESSION PT. NO.14) (THIS WELL WAS NO. 10 ON THE LEASE MAP)
(If additional description is necessary, use BACK of this form.)

I DID observe this plugging.

Signed:

Clayton P. Titel
TECHNICIAN

RECEIVED
AUG 29 2005
KCC WICHITA

Bu