

3 022829

15-001-02004 0000

To:

STATE CORPORATION COMMISSION

Wichita State Office Bldg. - PLUGGING SECTION

130 S. Market, Room 2078

Wichita, Kansas 67202

API NUMBER CONTROL NO. 20050040-010

SE,SW,SE 1/4 Sec/Twp/Rge S.21-T.25S.-R.18E.

292 feet from south section line

1477 feet from east section line

TECHNICIAN'S PLUGGING REPORT

Operator License #

101

Lease/Well# DOTY 10

County ALLEN

Operator: STATE OF KANSAS Fee Fund

Well Total Depth 900 feet

Name & FEE FUND PLUGGING

Production Pipe: 2" Size Feet 900'

Address

Surface Casing: 6 1/4" Size Feet 20'

AB oil well ☒ Gas Well ☐ SWD Well/ Input Well ☐

D & A

Other well as hereinafter indicated:

Plugging Contractor: KEPLEY WELL SERVICE, LLC

Lic. # 30670

Address: 19254 FORD ROAD, CHANUTE, KANSAS 66720

Company to plug at: Hour: 1:00P.M. Day: 11 Month: 8 2005

Plugging proposal received from: CLAYTON P. TITEL

Company Name: KANSAS CORPORATION COMMISSION Phone: 620-432-2300

Were: THIS WELL CONSISTED OF 2" CASING TO APPROXIMATELY 900' THAT HAD

BEEN CEMENTED IN FROM BOTTOM TO TOP. THE PLUGGING PROPOSAL WAS TO

CIRCULATE THE 2" CASING FULL OF CEMENT.

Plugging Proposal Received by:

CLAYTON P. TITEL

Plugging attended by Agent: All ☒ Part

TECHNICIAN

None

Operations Completed: Hour: 4:00P.M. Day: 11 Month: 8 2005

Actual Plugging Report: AN INSERT PUMP HAD BEEN LOST IN THE BOTTOM OF

THE 2" CASING. 1" PIPE WAS RAN INTO THE 2" CASING TO 850'. CEMENT WAS PUMPED

INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE 2" CASING AT SURFACE. THE

1" PIPE WAS REMOVED. DISPLACEMENT WAS FILLED FROM SURFACE. 56 SACKS OF

CEMENT WERE PUMPED INTO THIS WELL.

Remarks: (GPS SESSION PT. NO.10) (THIS WELL WAS NOT ILLUSTRATED ON THE LEASE MAP)

(If additional description is necessary, use BACK of this form.)

I DID observe this plugging.

Signed:


TECHNICIANRECEIVED
AUG 29 2005
KCC WICHITA