

3 022831

15-001-02003-00-00

To:

STATE CORPORATION COMMISSION

Wichita State Office Bldg. - PLUGGING SECTION

130 S. Market, Room 2078

Wichita, Kansas 67202

API NUMBER CONTROL NO. 20050040-015

NE,NW,SE 1/4 Sec/Twp/Rge S.21-T.25S.-R.18E.

2016 feet from south section line

1866 feet from east section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 101

Lease/Well# DOTY 9

County ALLEN

Operator: STATE OF KANSAS Fee Fund

Well Total Depth 900' feet

Name & FEE FUND PLUGGING

Production Pipe: 2" Size Feet 900'

Address

Surface Casing: 10" Size Feet 20'

AB oil well X Gas Well SWD Well/ Input Well

D & A

Other well as hereinafter indicated:

Plugging Contractor: KEPLEY WELL SERVICE, LLC

Lic. # 30670

Address: 19254 FORD ROAD, CHANUTE, KANSAS 66720

Company to plug at: Hour: 8:30A.M. Day: 9 Month: 8 2005

Plugging proposal received from: CLAYTON P. TITEL

Company Name: KANSAS CORPORATION COMMISSION Phone: 620-432-2300

Were: THIS WELL ORIGINALLY CONSISTED OF 2" CASING TO T.D. THAT HAD ONLY

BEEN PARTIALLY CEMENTED IN. AT SOME TIME IN THE PAST A 3" LINER HAD BEEN

SLEEVED OVER PART OF THE 2" CASING. THE PROPOSAL WAS TO PERFORATE THE

CASING AND TO CIRCULATE AS MUCH OF THE WELL AS POSSIBLE FULL OF CEMENT.

Plugging Proposal Received by: CLAYTON P. TITEL

Plugging attended by Agent: All Part None X

Operations Completed: Hour: 10:00P.M. Day: 9 Month: 8 2005

Actual Plugging Report: THE WELLS CASINGS WERE PERFORATED AT 200'

AND AT 500'. 1" PIPE WAS RAN INTO THE 2" CASING TO 850'. CEMENT WAS PUMPED

INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE 2" CASING AT SURFACE. THE

1" PIPE WAS REMOVED. 1" PIPE WAS RAN INTO THE 3" AND 10" ANNULUS TO 85'. AT

THAT DEPTH A SOLID OBSTRUCTION WAS ENCOUNTERED. CEMENT WAS PUMPED INTO

THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE WELL AT SURFACE. THE 1" PIPE

WAS REMOVED. 56 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

Remarks: (GPS SESSION PT. NO.15) (THIS WELL WAS NO. 9 ON THE LEASE MAP)

(If additional description is necessary, use BACK of this form.)

I DID NOT observe this plugging.

Signed:


 TECHNICIAN

 RECEIVED
 AUG 29 2005
 KCC WICHITA

