

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, Kansas 67202

Well Plugging Record
K.A.R. -82-3-117

API NUMBER 15-077-21529-00-00
LEASE NAME Black-Fankhauser "A"
WELL NUMBER 1-27

TYPE OR PRINT
NOTICE: Fill out completely and return
to Cons. Div. office within 30 days.
1980 Ft. from South Line of Section
2130 Ft. from East Line of Section

LEASE OPERATOR McCoy Petroleum Corporation SPOT LOCATION 150' W of NW SE
ADDRESS 8080 E. Central, Suite 300 Section 27 Township 32s Range 8w
CITY, STATE, ZIP Wichita, Kansas 67206 County Harper
PHONE # 316-636-2737 Date Well Completed 09/28/05
Character of Well Dry and Abandoned Date Plugging Commenced 09/28/05
(Oil, Gas, D&A, SWD, Input, Water Supply Well) Date Plugging Completed 09/28/05

The plugging proposal was approved on 09/26/05 (date)
by Butch Hoberecht (KCC District Agent's Name)
Is ACO-1 Filed? ? If not, is well log attached? Yes
Producing Formation(s) D&A Depth to Top Bottom T.D. 4525
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULL OUT
Surface Soil and Sands		0	60			
Redbeds	Shale	60	255	8-5/8"	242'	0'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Plugged well with heavy mud from 4525' to 1200', then 50 sx at 1200', 50 sx at 800', 35 sx at 300' and 25 sx at 60' to surface. Plugged rathole with 15 sacks, no mousehole. Total cement used = 175 sx of 60/40 Poz with 4% Gel. Plugging completed at 4:15 pm on 09/28/05. Acid Services Ticket # 11720. Received plugging orders from Butch Hoberecht at 4:45 pm on 09/26/05. Sterling Drilling reported to KCC on 09/29/05.

Name of Plugging Contractor Sterling Drilling Company
Licence No. 5142
Address P.O. Box 1006 City: Pratt State: Kansas Zip 67124
NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: McCoy Petroleum Corporation (Operator)


STATE OF KANSAS COUNTY OF PRATT, ss.

Gary M. Talbott, Agent (Employee of Operator or (Operator) of above described well, being first
duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of
the above described well as filed that the same are true and correct, so help me God.

(Signature) *Gary M. Talbott*
(Gary M. Talbott, Vice- President of Sterling Drilling Company)

(Address) P.O. Box 1006 City: Pratt State: Kansas Zip 67124

SUBSCRIBED AND SWORN TO me this 4TH day of OCT, 2005



Carol I. Mott
(Notary Public)

My Commission Expires: 03-29-08

Bun

RECEIVED
OCT 05 2005
KCC WICHITA

Sterling Drilling Company, Rig #4

Box 1006, Pratt, Kansas 67124-1006
Office Phone (620) 672-9508, Fax 672-9509

SAMPLE LOG

Black-Fankhauser "A" 1-27

LOCATION: 150' W of NW SE
API: 15-077-21529-00-00

Section 27 T 32s R 8w
Harper County, Kansas

OWNER: McCoy Petroleum Corporation
CONTRACTOR: Sterling Drilling Company, Rig #4

COMMENCED: 09/19/05
COMPLETED: 09/28/05

TOTAL DEPTH:	DRILLER	4525	FEET
	LOGGER	4522	FEET

Ground Elevation: 1391
KB Elevation: 1400

LOG

0 -	3 FEET	Top Soil
3 -	60 FEET	Sandy Clay
60 -	1120 FEET	Redbeds
1120 -	1640 FEET	Shales and Salt
1640 -	4525 FEET	Limestone/Shales

CASING RECORDS

Surface Casing:

Spud at 6:00 pm on 09/19/05. Drilled 12-1/4" hole to 255'. Ran 6 joints of new 23# 8-5/8" surface casing tallied 241.87' set at 252.87' KB. Cemented with 225 sx 60/40 Poz, 2% Gel, 3% CC,. Plug down at 4:15 am on 09/20/05 by Acid Services. Ticket #11715. Cement did circulate. Strapped bottom 2 joints, of SP, then welded collars on next 4 joints.

Plugging Data:

Plugged well with heavy mud from 4525' to 1200', then 50 sx at 1200', 50 sx at 800', 35 sx at 300' and 25 sx at 60' to surface. Plugged rathole with 15 sacks, no mousehole. Total cement used = 175 sx of 60/40 Poz with 4% Gel. Plugging completed at 4:15 pm on 09/28/05. Acid Services Ticket # 11720. Received plugging orders from Butch Hoberecht at 4:45 pm on 09/26/05. Sterling Drilling reported to KCC on 09/29/05.

DEVIATION SURVEYS

3/4 degree(s) at 255 feet
1/4 degree(s) at 4465 feet

RECEIVED
OCT 05 2005
KCC WICHITA