

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: Bear Petroleum, Inc.  
Address: P.O. Box 438, Haysville, KS 67060  
Phone: (316) 524-1225 Operator License #: 4419  
Type of Well: Oil Docket #: \_\_\_\_\_  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (if SWD or ENHR)  
The plugging proposal was approved on: 10-7-04 (Date)  
by: Butch Hoberecht (KCC District Agent's Name)  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
Arbuckle Depth to Top: 3404 Bottom: 3410 T.D. 3410  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15-035-20539-00-00  
Lease Name: E. L. Morris  
Well Number: 1B  
Spot Location (QQQQ): NW-SW-NW  
3630 Feet from  North /  South Section Line  
4950 Feet from  East /  West Section Line  
Sec. 35 Twp. 31 S. R. 4  East  West  
County: Cowley  
Date Well Completed: NA  
Plugging Commenced: 9-8-05  
Plugging Completed: 9-30-05

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Surface	8 5/8"	Surface	201	8 5/8"	201	0
Production	4 1/2"	Surface	3404	4 1/2"	3404	900'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Sand back from TD 3410' to 3350', dump bail 4 sax cement on plug, worked pipe and shot off at 900', pulled pipe, ran in hole 1 1/4" poly pipe to 225', circulated 125 sax 60/40 poz to surface, pull out of hole poly pipe, and topped off with 25 sax.

Name of Plugging Contractor: Braden Petroleum & Well Plugging Co., BPC Well Plugging License #: 32475  
Address: P.O. Box 282, Burden, KS 67019  
Name of Party Responsible for Plugging Fees: Bear Petroleum, Inc.  
State of Kansas County, Sedgwick, ss.

R. A. Schremmer (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) \_\_\_\_\_  
(Address) P.O. Box 438, Haysville, KS 67060

SUBSCRIBED and SWORN TO before me this 6th day of October, 20 05

**SHANNON HOWLAND**  
Notary Public - State of Kansas  
My Appt. Expires 3/10/08

Shannon Howland My Commission Expires: 3/10/08  
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED  
OCT 07 2005  
KCC WICHITA

*Bm*



