

State of Kansas



FORM CP-2

15-123-20007-00-00

JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
245 North Water
WICHITA, KANSAS 67202

March 28, 1981

VERBAL PERMIT FORM (To be filed by Plugging Agent)

Dear Sir:

Mr. Bruce Fickel of Emphasis Oil Operations has this date requested permission to plug the following described well:

Operator's Full Name: Maralo, Inc.

Complete Address: P.O. Nox 832, Midland, Texas

Lease Name: Golladay Well No. 1

Location: C SW SW Sec. 19 Twp. 7 Rge. 7 (E) (W)

County: Mitchell Total Depth: 2714'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: _____

Mr. Fickel was instructed to plug the well as follows:

8-5/8"-255'-100 sacks 2% gel 3% cal chloride. Fill hole with mud.

Pump 50 sacks 50-50 Pozmix w/4% gel and 3% cal chloride through drill

pipe at 450'. Pump 25 sacks cement through drill pipe at 250'. Fill

hole with mud to 40'. Push plug and 1/2 sack hulls to 40' and cap hole

with 10 sacks cement. Cement rathole with 5 sacks cement.

Very truly yours,

Conservation Division Agent

RECEIVED
STATE CORPORATION COMMISSION

APR - 3 1981

4-3-81
CONSERVATION DIVISION
Wichita, Kansas