

State of Kansas



15-181-20001-00-60

ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS 67202

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

J. Lewis Brock
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

RECEIVED
 STATE CORPORATION COMMISSION
 NOV 20 1968
 CONSERVATION DIVISION
 Wichita, Kansas

Dear Sir:

Mr. A. L. Thompson of Mack Oil Company, has this date requested permission to plug the following described well:

Mr. Thompson guarantees payment of the plugging fee.

Operator's full Name: Mack Oil Company,

Complete Address: 812 Union Center Building, Wichita, Kansas.

Lease Name: Seaman Well No. 1

Location: CSW-SW Sec. 17 Twp. 6 Rge. (E)(W) 40

County: Sherman Total Depth 3691 Oil Well

Gas Well Input Well SWD Well D & A Lost Hole X

Mr. Thompson was instructed to plug the well as follows:

393ft--8 5/8" Surface casing, cement circulated with 350 Sx.
Top of Dakota section @ 2400'. DP was on bottom, pipe was backed off
app. 450' off bottom and wash-over pipe run. Stuck washover string and
it was decided to abandon hole.
Circulate hole with heavy mud. Pull DP to 2680' and displace 120 Sx.
cement thru DP. Pull DP to 420' and displace 20 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

Very truly yours,


 Conservation Division Agent