

State of Kansas



FORM CP-2

15-141-20149-00-00

JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
Wichita, Kansas 67202

RECEIVED 5, 1982
SEP 17 1982
CONSERVATION DIVISION
Wichita, Kansas

VERBAL PERMIT FORM
(To be filed by Plugging Agent)

9-17-82

Dear Sir:

Mr. Burton Beery of Shields Drilling Co. has this date requested permission to plug the following described well:

Operator's Full Name: Shields Oil Producers

Complete Address: Shields Bldg., Russell, Kansas 67665

Lease Name: Enoch Well No. 3

Location: SW SW Sec. 32 Twp. 7 Rge. 15 (E) (W)

County: Osborne Total Depth: 3325'

Abandoned Oil Well ☐ Gas Well ☐ Input Well ☐ SWD Well ☐ D&A ☒

Other well as hereafter indicated: _____

Mr. Beery was instructed to plug the well as follows:

Anhydrite 1180'-1218' Circulate hole and Fill with mud. Pump
50 sacks cement through drill pipe at 900'. Pump 30 sacks
Cement through drill pipe at 275'. Fill hole with mud to
40'. Push plug and 1/2 sack hulls to 40' and cap hole with
10 sacks cement. Cement Rathole with 10 sacks cement.
Cement mousehole with 10 sacks cement.

Very truly yours,

William J. Larson
Conservation Division Agent