

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-053-20775-00-00
Spot: NWSESE Sec/Twnshp/Rge: 33-16S-10W
990 feet from S Section Line, 1320 feet from E Section Line
Lease Name: STOLTENBERG Well #: 9
County: ELLSWORTH Total Vertical Depth: 3313 feet

Operator License No.: 5358
Op Name: B.L.G. CO. A GENERAL PARTNERSHIP
Address: PO BOX 214
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3282	1300	250 SX CMT
SURF	8.625	409		190 SX CMT

#107⁶⁷

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/29/2005 10:00 AM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: KIRK GLENN Company: D S & W WELL SERVICING, INC. Phone: (620) 587-3361

Proposed Plugging Method: Sand open hole to 3230' and cap with 5 sxs; cut off casing @ 1350' and pump 35 sxs; pull casing to 1000' and pump 35 sxs; pull casing to 460' and circ to surf.

Plugging Proposal Received By: MICHAEL WILSON WitnessType: PARTIAL
Date/Time Plugging Completed: 08/29/2005 12:30 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Sanded open hole to 3230' and capped with 5 sacks of cement. Cut off casing at 1300' and pumped 35 sacks of cement. Pulled casing to 1000' and pumped 35 sacks of cement. Pulled casing to 460' and circulated cement to surface.

Copeland Cement #26057

60/40 posmix with 4% gel

Perfs:

RECEIVED
KCC DISTRICT #2
SEP - 1 2005
WICHITA, KS

Remarks:

Plugged through: CSG

District: 02

Signed

Virgil Clothier
(TECHNICIAN)

INVOICED

DATE 10-12-05

INV. NO. 2006060601

RECEIVED

OCT 12 2005

KCC WICHITA