

TO:  
 STATE CORPORATION COMMISSION  
 CONSERVATION DIVISION - PLUGGING  
 130 SOUTH MARKET, SUITE 2078  
 WICHITA, KANSAS 67202

API Well Number: 15-145-21478-00-00  
 Spot: S2NWNE Sec/Twnshp/Rge: 2-20S-16W  
990 feet from N Section Line, 1980 feet from E Section Line  
 Lease Name: AMIL Well #: 1  
 County: PAWNEE Total Vertical Depth: 3850 feet

Operator License No.: 30337  
 Op Name: SPECIAL ENERGY CORP.  
 Address: PO BOX 369  
STILLWATER, OK 74076

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	7	3850	2640	WITH 150 SX CMT
SURF	9.625	1030		WITH 275 SX CMT

\$125<sup>13</sup>

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/30/2005 11:30 AM  
 Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
 Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 786-2001

Proposed Plugging Method: SAND TO 3600' & 7 SX CMT. PLUG AT 1060' WITH 25 SX GEL & 60 SX CMT. PLUG AT 660' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY WitnessType: COMPLETE (100%)  
 Date/Time Plugging Completed: 09/30/2005 1:15 PM KCC Agent: RICHARD LACEY

**Actual Plugging Report:**

SANDED TO 3600' & 7 SX CMT WITH BAILER. SPOTTED PLUGS THROUGH TUBING. 1ST PLUG AT 1060' WITH 25 SX GEL & 60 SX CMT. 2ND PLUG AT 660' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT.

**Perfs:**


Top	Bot	Thru	Comments
3792	3793		
3775	3776		
3706	3768		
3678	3680		
3668	3688		

RECEIVED  
 OCT 07 2005  
 KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED.

Plugged through: TBG

District: 01



Signed \_\_\_\_\_

*Richard M. Lacey*  
 (TECHNICIAN)

INVOICED  
 DATE 10-7-05  
 INV. NO. 20060605.99

Form CR 23