

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-21471-00-00
Spot: SESWNE Sec/Twnshp/Rge: 9-16S-13W
2970 feet from S Section Line, 1650 feet from E Section Line
Lease Name: DEUTSCH Well #: 7
County: BARTON Total Vertical Depth: 3372 feet

Operator License No.: 30380
Op Name: HUPFER OPERATING, INC.
Address: PO BOX 216
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3368	0	UNKNOWN
SURF	8.625	240	0	UNKNOWN

#109⁵⁹

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/10/2005 9:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: DENNIS D HUPGER & MIK Company: HUPFER OPERATING, INC. Phone: (785) 628-8666

Proposed Plugging Method: Ordered 250 sxs 60/40 pozmix - 10% gel - 600# hulls.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/10/2005 11:30 AM KCC Agent: PAT STAAB

Actual Plugging Report:

Mike's Testing sanded off bottom to 3300' and topped with 4 sxs cement using a dump bailer.
Cut 4 1/2" casing at 1500' - 1400' - 1200' - 1000' - casing would not come free.
Copeland rigged to casing and pumped 40 sxs neat followed with 100 sxs cement with 150# hulls mixed in.
Max. P.S.I. 800#. S.I.P. 450#.
Mike's Testing backed off casing three joints.
Copeland rigged to 8 5/8" casing with a swedge and pumped 50 sxs cement.
Max. P.S.I. 700#. S.I.P. 525#.

Perfs:

Top	Bot	Thru	Comments
3368	3372	OH	

Remarks: COPELAND ACID & CEMENTING COMPANY-TICKET #26159.

Plugged through: CSG

District: 04

Signed

Pat Staab

(TECHNICIAN)

RECEIVED

OCT 13 2005

KCC WICHITA

INVOICED

OCT 10 2005

DATE

10-13-05

INV. NO.

20060601613

