

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-25456-00-00
Spot: N2SWSWSW Sec/Twnshp/Rge: 20-12S-16W
550 feet from S Section Line, 330 feet from W Section Line
Lease Name: BURGHARDT Well #: 1
County: ELLIS Total Vertical Depth: 3660 feet

Operator License No.: 6246
Op Name: BENNETT & SCHULTE OIL CO., A GEN
Address: 140 WEST WICHITA AVE.
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	210		

118⁹⁵

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 10/03/2005 4:25 PM
Plug Co. License No.: 9431 Plug Co. Name: VONFELDT DRILLING, INC
Proposal Rcvd. from: DOUG BUDIG Company: VONFELDT DRILLING, INC Phone: (785) 483-6446

Proposed Plugging Method: Ordered 225 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: EDWIN SCHUMACHER WitnessType: NONE
Date/Time Plugging Completed: 10/04/2005 5:00 PM KCC Agent: EDWIN SCHUMACHER

Actual Plugging Report:

Perfs:

1st. Plug at 3620' w/25 sxs.
2nd. Plug at 1300' w/25 sxs.
3rd. Plug at 800' w/100 sxs.
4th. Plug at 260'w/40 sxs.
5th. Plug at 40'w/10 sxs.
Rathole with 15 sxs.
Mousehole with 10 sxs.

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed

Ed Schumacher

(TECHNICIAN)

INVOICED

RECEIVED

OCT 11 2005

OCT 07 2005

DATE

10-12-05

KCC WICHITA

TEL NO

2006660602