

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-159-21834-00-00  
Spot: SWNESW Sec/Twnshp/Rge: 31-18S-7W  
1632 feet from S Section Line, 3733 feet from E Section Line  
Lease Name: BOLTON Well #: 9  
County: RICE Total Vertical Depth: 3314 feet

Operator License No.: 30364  
Op Name: RESOURCE OPERATIONS, INC.  
Address: BOX 9487  
TULSA, OK 74157

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3313	1700	160 SX CMT
SURF	8.625	214		150 SX CMT

#107.71

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/15/2005 3:00 PM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Revd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 562-8088

Proposed Plugging Method: Sand perfs to 3180' and put 5 sxs on top; cut off casing; pull to 1050' and pump 35 sxs; pull casing to 700' and pump 35 sacks; pull casing to 265' and circ to surface.

Plugging Proposal Received By: MICHAEL WILSON WitnessType: NONE  
Date/Time Plugging Completed: 09/15/2005 6:30 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Sanded perforations to 3180' and put 5 sacks of cement on top. Cut off casing at 1700'. Pulled casing to 1050' and pumped 35 sacks of cement with 100 lbs of cotton hulls. Pulled casing to 700' and pumped 35 sacks of cement with 100 lbs of cotton hulls. Pulled casing to 265' and circulated cement to surface.

290 sacks of 60/40 posmix with 4% gel

Allied Cement #17573

Perfs:

Top	Bot	Thru	Comments
3232	3235		

RECEIVED  
KCC DISTRICT #2  
SEP 26 2005  
WICHITA, KS

Remarks:

Plugged through: CSG

District: 02

Signed Virgil Clothier  
(TECHNICIAN)

INVOICED  
DATE 10-12-05  
INV. NO. 2006060604

RECEIVED  
OCT 12 2005  
KCC WICHITA