

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-21652-00-00
Spot: NENESE Sec/Twnshp/Rge: 20-19S-9W
1994 feet from S Section Line, 409 feet from E Section Line
Lease Name: CHAPPELL Well #: 1
County: RICE Total Vertical Depth: 3331 feet

Operator License No.: 30364
Op Name: RESOURCE OPERATIONS, INC.
Address: BOX 9487
TULSA, OK 74157

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3330	1250	325 SX CMT
SURF	8.625	224		180 SX CMT

#108²⁶

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/13/2005 2:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 562-8088

Proposed Plugging Method: See actual report.

RECEIVED
KCC DISTRICT #2
SEP 26 2005
WICHITA, KS

Plugging Proposal Received By: VIRGIL CLOTHIER WitnessType: NONE
Date/Time Plugging Completed: 09/13/2005 3:15 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Sanded perforations to 3180' and put 5 sacks of cement on top. Cut off casing at 1250' and pulled to surface. Ran tubing to 1200' and pumped 35 sacks of cement. Pulled tubing to 800' and pumped 35 sacks of cement. Pulled tubing to 275' and circulated cement to surface.

Perfs:

Top	Bot	Thru	Comments
3263	3265		
3230	3232		
3224	3322		

Remarks:

Plugged through: TBG

District: 02

Signed

Virgil Clothier
(TECHNICIAN)

INVOICED
DATE 10-12-05
INV. NO. 2006060604

RECEIVED
OCT 12 2005
KCC WICHITA