

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-159-20898-00-00  
Spot: SENESW Sec/Twnshp/Rge: 29-19S-10W  
1650 feet from S Section Line, 2970 feet from E Section Line  
Lease Name: BAYER SARA Well #: 2  
County: RICE Total Vertical Depth: 3390 feet

KCC  
BEM  
10-12-05  
RBDMS  
D.D.11

Operator License No.: 30364  
Op Name: RESOURCE OPERATIONS, INC.  
Address: BOX 9487  
TULSA, OK 74157

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3387	1329	150 SX CMT
SURF	8.625	245		175 SX CMT

#110 18

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/12/2005 11:00 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 562-8088

Proposed Plugging Method: See actual report.

Plugging Proposal Received By: VIRGIL CLOTHIER WitnessType: PARTIAL  
Date/Time Plugging Completed: 09/12/2005 1:30 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Sanded perforations to 3280' and capped with 4 sacks of cement. Cut off casing at 1329'. Pulled casing to 1250' and pumped 35 sacks of cement with 100 lbs of cotton hulls. Pulled casing to 900' and pumped 35 sacks of cement with 100 lbs of cotton hulls. Pulled casing to 300' and circulated cement to surface.

60/40 posmix with 4% gel

Allied Cement #22502

Perfs:

Top	Bot	Thru	Comments
3331	3390		

RECEIVED  
KCC DISTRICT #2  
SEP 26 2005  
WICHITA, KS

Remarks:

Plugged through: CSG

District: 02

Signed Virgil Clothier  
(TECHNICIAN)

INVOICED  
DATE 10-12-05  
INV. NO. 2006060604

RECEIVED  
OCT 12 2005  
KCC WICHITA