

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-20948-00-00
Spot: NWSW Sec/Twnshp/Rge: 13-9S-23W
1980 feet from S Section Line, 4620 feet from E Section Line
Lease Name: LAW E Well #: 1
County: GRAHAM Total Vertical Depth: 3946 feet

Operator License No.: 30537
Op Name: VENTURE RESOURCES, INC.
Address: 2110 S. GILPIN PO BOX 101234
DENVER, CO 30250

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3940	0	w/175 sxs cmt
SURF	8.625	165	0	w/160 sxs cmt

#128²⁵

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/05/2005 1:00 PM
Plug Co. License No.: 32028 Plug Co. Name: CHITO'S WELL SERVICE, LLC
Proposal Rcvd. from: JOHN CEARLEY Company: VENTURE RESOURCES, INC. Phone: (303) 722-2899

Proposed
Plugging
Method:

Ordered 300 sxs cement and 500# hulls.

Plugging Proposal Received By: ROGER MOSES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/05/2005 3:30 PM KCC Agent: ROGER MOSES

Actual Plugging Report:

Perfs:

Tied to 8 5/8" x 4 1/2" - squeezed 55 sxs cement to Max. P.S.I. 100# - hole in casing.
Tied to 4 1/2" casing - squeezed 210 sxs cement with 500# hulls.
Max. P.S.I. 200#. S.I.P. 200#.
Tied back to annulus - squeezed 10 additional sxs cement.
Max. P.S.I. 150# S.I.P. 150#.
Total of 275 sxs 60/40 pozmix - 10% gel - 500# hulls.

Remarks: SWIFT SERVICES, INC. J&M TANK & ATS-WATER.

Plugged through: CSG

District: 04

Signed

Roger L. Moses

(TECHNICIAN)

RECEIVED

OCT 11 2005

KCC WICHITA

INVOICED

DATE

10-12-05

REF. NO.

2006060606

OCT 06 2005

Form CP-2/3

3310471

DON E. PRATT

P.O. BOX 370, HAYS, KS.

#1 LAW "E"

13-9-23W
C NW SW

CONTR MURFIN DR LG. CO.

CTY GRAHAM

GEOL GREEN & GREEN

FIELD WC (MARSHALL LAW DISC.)

E 2362 KB CM 8/26/77

CARD

ISSUED 10/13/77

P 113 BOPD. NW

LANS 3820-24

+	+	+	+
+	+	+	+

API 15-065-20,948

SMP	TOPS	DEPTH	DATUM
TQP	3409	-1047	
HEEB	3628	-1266	
TQR	3649	-1287	
LANS	3662	-1300	
RTD	3946	-1584	

8-5/8" 165/160sx, 4 1/2" 3940/175sx
 DST (1) 3686-3733 (LANS)/30-30-30-30,
 20' M, SIP 551-438#, FP 42-42#
 DST (2) 3809-70 (LANS)/30-30-30-30,
 480' O, SIP 1270-1254#, FP 62-211#
 MICT - CO, PF (LANS) 3820-24, AC 500,
 SWB DWN & SWB 34 BO/2 HRS, POP

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS