

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-179-21140-00-00
Spot: NENWSE Sec/Twnshp/Rge: 26-9S-26W
2280 feet from S Section Line, 1600 feet from E Section Line
Lease Name: TRANSUE Well #: 1
County: SHERIDAN Total Vertical Depth: 4140 feet

Operator License No.: 31900
Op Name: NOR-WEST KANSAS OIL, L.L.C.
Address: RR 2, BOX 14
WAKEENEY, KS 67672

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	274		

#134⁵⁵

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 10/03/2005 4:35 PM
Plug Co. License No.: 33237 Plug Co. Name: ANDERSON, C. D. DBA ANDERSON DRILLING
Proposal Rcvd. from: DARRELL ANDERSON Company: NOR-WEST KANSAS OIL, LLC Phone: (785) 743-2769

Proposed Plugging Method: Ordered 190 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: EDWIN SCHUMACHER Witness Type: NONE
Date/Time Plugging Completed: 10/04/2005 2:30 AM KCC Agent: EDWIN SCHUMACHER

Actual Plugging Report:

Perfs:

1st. Plug at 2285' w/25 sxs.
2nd. Plug at 1345' w/100 sxs.
3rd. Plug at 315' w/40 sxs.
4th. Plug at 40' w/10 sxs.
Rathole with 15 sxs.

RECEIVED
OCT 07 2005
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04



Signed Ed Schumacher
(TECHNICIAN)

INVOICED

DATE 10-7-05

TEL. NO. 2006060596

OCT 05 2005