

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-207-26904-00-00  
Spot: E2E2E2SW Sec/Twnshp/Rge: 30-25S-14E  
1300 feet from S Section Line, 2460 feet from W Section Line  
Lease Name: NORDMEYER Well #: 21-05  
County: WOODSON Total Vertical Depth: 1338 feet

Operator License No.: 30345  
Op Name: PIQUA PETRO, INC.  
Address: 1331 XYLAN ROAD  
PIQUA, KS 66761

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	7	40		

#43.49

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/08/2005 10:00 AM  
Plug Co. License No.: 31440 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES, INC  
Proposal Rcvd. from: ADAM SPLECTER Company: PIQUA PETRO, INC. Phone: (620) 433-0099

Proposed Plugging Method: THIS WELL CONSISTED OF AN UNCASD BORE TO 1338. THE PLUGGING PROPOSAL WAS TO PLACE A 50' CEMENT PLUG AT T.D. A 50' CEMENT PLUG AT 700', AND A CONTINUOUS CEMENT PLUG FROM 200' TO SURFACE.

Plugging Proposal Received By: CLAYTON TITEL WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 09/08/2005 12:00 PM KCC Agent: CLAYTON TITEL

Actual Plugging Report:

Perfs:

2 7/8" PIPE WAS RAN INTO THE WELL TO T.D.. 20 SACKS OF CEMENT WERE PUMPED THROUGH THE 2 7/8" TUBING TO T.D.. THE 2 7/8" PIPE WAS PULLED TO 700' AND 10 SACKS OF CEMENT WRER PUMPED TO THAT DEPTH. THE TUBING WAS PULLED TO 200'. CEMENT WAS PUMPED INTO THE 2 7/8" TUBING UNTIL CEMENT CIRCULATED FROM THE SURFACE CASING AT SURFACE. THE TUBING WAS REMOVED. DISPLACEMENT WAS FILLED FROM SURFACE. CEMENT WAS PUMPED BY CONSOLIDATED OIL WELL SERVICES, INC.

RECEIVED  
KCC DISTRICT #3

SEP 9 2005 CPT

CHANUTE, KS

Remarks:

Plugged through: TBG

District: 03

Signed

Clayton R. Titel  
(TECHNICIAN)

RECEIVED  
OCT 17 2005  
KCC WICHITA

INVOICED  
DATE 10-18-05  
INV. NO 2006060631