

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-00831-00-00
Spot: NENENW Sec/Twnshp/Rge: 33-29S-7W
300 feet from N Section Line, 2970 feet from E Section Line
Lease Name: FERN CAMPBELL Well #: 1
County: KINGMAN Total Vertical Depth: 4270 feet

Operator License No.: 31191
Op Name: R & B OIL & GAS, INC.
Address: 904 N. LOGAN PO BOX 195
ATTICA, KS 67009

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	4270	2620	125 SX CMT
SURF	8.625	253		160 SX CMT

#13878

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/15/2005 1:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Revd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: Perfs were 4177' - 4185', 4200' - 4220'. Sand to 4120' and 5 sxs cement. Recover casing. 35 sxs @ 1250'; 35 sxs @ 750'; and circ cement from 300'.

Plugging Proposal Received By: DONALD HOBERECHT WitnessType: NONE
Date/Time Plugging Completed: 06/15/2005 5:00 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

The perforations were covered with sand from TD to 4120' and capped with 5 sacks of cement. The casing was ripped at 2810' and 2620'. Pulled casing from 2620' to 1250' and spotted 35 sacks of cement. Pulled casing to 750' and spotted 35 sacks of cement. Pulled casing to 300' and cement was circulated to surface.

60/40 posmix with 4% gel

Allied Cementing

Perfs:

Top	Bot	Thru	Comments
4200	4220		
4177	4185		

**RECEIVED
KCC DISTRICT #2
OCT 5 - 2005
WICHITA, KS**

Remarks:
Plugged through: CSG

District: 02 Signed  (TECHNICIAN)

INVOICED
DATE 10-13-05
INV. NO. 2006060615

RECEIVED
OCT 13 2005
KCC WICHITA